


NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS  
PARKS POND DAM (CT 00..U) CORPS OF ENGINEERS WALTHAM  
MA NEW ENGLAND DIV JUL 80

1 / 1

F/G 13/13 NL

END  
DATE  
FILMED  
8-84  
DTIC





MICROCOPY RESOLUTION TEST CHART  
NATIONAL BUREAU OF STANDARDS-1963-A



AD-A142 878

HOUSATONIC RIVER BASIN  
DANBURY CONNECTICUT

# PARKS POND DAM CT 00071

## PHASE I INSPECTION REPORT NATIONAL DAM INSPECTION PROGRAM



DEPARTMENT OF THE ARMY  
NEW ENGLAND DIVISION, CORPS OF ENGINEERS  
WALTHAM, MASS. 02154

DTIC  
ELECTRONIC  
S JUL 9 1984  
A

DTIC FILE COPY

JULY 1980

84 07 02 101

This document has been approved  
for public release and sale; its  
distribution is unlimited.



UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER CT 00071	2. GOVT ACCESSION NO. AD-A142878	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Housatonic River Basin Danbury Conn., Parks Pond Dam NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS		5. TYPE OF REPORT & PERIOD COVERED INSPECTION REPORT
7. AUTHOR(s) U.S. ARMY CORPS OF ENGINEERS NEW ENGLAND DIVISION		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS		8. CONTRACT OR GRANT NUMBER(s)
11. CONTROLLING OFFICE NAME AND ADDRESS DEPT. OF THE ARMY, CORPS OF ENGINEERS NEW ENGLAND DIVISION, NEDED 424 TRAPELO ROAD, WALTHAM, MA. 02254		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		12. REPORT DATE July 1980
		13. NUMBER OF PAGES 55
		15. SECURITY CLASS. (of this report) UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) APPROVAL FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES Cover program reads: Phase I Inspection Report, National Dam Inspection Program; however, the official title of the program is: National Program for Inspection of Non-Federal Dams; use cover date for date of report.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) DAMS, INSPECTION, DAM SAFETY,  Housatonic River Basin Danbury Conn., Parks Pond Dam		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) Parks Pond Dam is a cyclopean masonry/earth embankment that is approx. 180 ft. long and 12 ft. high. The earth embankment is on the downstream side and has a 2:1 slope. The upstream face is cyclopean masonry with a vertical face. The spillway is located on the southern half of the dam and consists of a 30.5 ft. long weir. There is a lower gate house for the control of a discharge pipe that passes through the base of the dam. The size of the pipe is unknown. The balve for the operation of the discharge pipe is inoperable. The drainage area is 0.5 square miles and the reservoir has 100 acre-feet of available storage.		





DEPARTMENT OF THE ARMY  
NEW ENGLAND DIVISION, CORPS OF ENGINEERS  
424 TRAPELO ROAD  
WALTHAM, MASSACHUSETTS 02154

REPLY TO  
ATTENTION OF:  
NEDED

8 OCT 1980

Honorable Ella T. Grasso  
Governor of the State of Connecticut  
State Capitol  
Hartford, Connecticut 06115

Dear Governor Grasso:

Inclosed is a copy of the Parks Pond Dam Phase I Inspection Report, which was prepared under the National Program for Inspection of Non-Federal Dams. This report is presented for your use and is based upon a visual inspection, a review of the past performance and a brief hydrological study of the dam. A brief assessment is included at the beginning of the report. I have approved the report and support the findings and recommendations described in Section 7 and ask that you keep me informed of the actions taken to implement them. This follow-up action is a vitally important part of this program.

A copy of this report has been forwarded to the Department of Environmental Protection, the cooperating agency for the State of Connecticut. In addition, a copy of the report has also been furnished the owner, Mr. Paul d'Evegne, 21 Sunset Drive, Danbury, Connecticut 06810.

Copies of this report will be made available to the public, upon request, by this office under the Freedom of Information Act. In the case of this report the release date will be thirty days from the date of this letter.

I wish to take this opportunity to thank you and the Department of Environmental Protection for your cooperation in carrying out this program.

Sincerely,

  
MAX B. SCHEIDER

Colonel, Corps of Engineers  
Division Engineer

Incl  
As stated



**PARKS POND DAM**

CT 00071

HOUSATONIC RIVER BASIN

**DANBURY, CONNECTICUT**

PHASE I INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM

	001	<input checked="" type="checkbox"/>
	002	<input type="checkbox"/>
	003	<input type="checkbox"/>
	004	
	005	
	006	
	007	
	008	
	009	
	010	
	011	
	012	
	013	
	014	
	015	
	016	
	017	
	018	
	019	
	020	
	021	
	022	
	023	
	024	
	025	
	026	
	027	
	028	
	029	
	030	
	031	
	032	
	033	
	034	
	035	
	036	
	037	
	038	
	039	
	040	
	041	
	042	
	043	
	044	
	045	
	046	
	047	
	048	
	049	
	050	
	051	
	052	
	053	
	054	
	055	
	056	
	057	
	058	
	059	
	060	
	061	
	062	
	063	
	064	
	065	
	066	
	067	
	068	
	069	
	070	
	071	
	072	
	073	
	074	
	075	
	076	
	077	
	078	
	079	
	080	
	081	
	082	
	083	
	084	
	085	
	086	
	087	
	088	
	089	
	090	
	091	
	092	
	093	
	094	
	095	
	096	
	097	
	098	
	099	
	100	

COPIES  
REMOVED

A



## NATIONAL DAM INSPECTION PROGRAM

### PHASE I INSPECTION REPORT

Identification Number:	CT 00071
Name:	Parks Pond Dam
Town:	Danbury
County and State:	Fairfield County, Connecticut
Stream:	Parks Pond Brook
Date of Inspection:	April 22, 1980

### BRIEF ASSESSMENT

Parks Pond Dam is a cyclopean masonry/earth embankment that is approximately 180 feet long and 12 feet high. The earth embankment is on the downstream side and has a 2:1 slope. The upstream face is cyclopean masonry with a vertical face. The spillway is located on the southern half of the dam and consists of a 30.5-foot long weir. There is a lower gate house for the control of a discharge pipe that passes through the base of the dam. The size of the pipe is unknown. The valve for the operation of the discharge pipe is inoperable. The drainage area is 0.5 square miles and the reservoir has 100 acre-feet of available storage.

The assessment of the dam is based on the visual inspection, past operational performance and hydraulic/hydrologic computations. The dam is judged to be in poor condition with several areas that require attention. These areas include seepage through the dam and around the spillway's west training wall, deteriorated concrete of the spillway and upstream face of the dam, vegetation on the embankments and along the toe of the dam and the nonoperating status of the blowoff.


The dam is classified as small and has a significant hazard potential in accordance with guidelines established by the Corps of Engineers. The test flood for this dam is 1/2 the Probable Maximum Flood (PMF). The test




flood inflow is 625 cfs and the routed test flood outflow is 473 cfs. The test flood outflow will overtop the dam by 0.55 feet.

It is recommended that the owner engage the services of a qualified registered engineer experienced in the design of dams to investigate the seepage through the dam, prepare a detailed hydraulic/hydrologic study to determine the spillway's adequacy, and remove trees from the embankment. It is also recommended that the owner clear the debris from the spillway channel; remove vegetation from the downstream face and toe; repair the discharge valve and concrete; establish a formal warning system; and initiate a program of operation and maintenance and an annual inspection program.

The owner should implement the recommendations and remedial measures described above and in greater detail in Section 7 within one year after receipt of this Phase I Inspection Report.

  
Joseph F. Merluzzo  
Connecticut P.E. #7639  
Project Manager

  
Gary J. Giroux  
Connecticut P.E. #11477  
Project Engineer



This Phase I Inspection Report on PARKS POND DAM  
has been reviewed by the undersigned Review Board members. In our  
opinion, the reported findings, conclusions, and recommendations are  
consistent with the Recommended Guidelines for Safety Inspection of  
Dams, and with good engineering judgment and practice, and is hereby  
submitted for approval.

*Richard J. Di Bruno*

RICHARD DIBUONO, MEMBER  
Water Control Branch  
Engineering Division

*Aramast Mahtesian*

ARAMAST MAHTESIAN, MEMBER  
Geotechnical Engineering Branch  
Engineering Division

*Carney M. Terzian*

CARNEY M. TERZIAN, CHAIRMAN  
Design Branch  
Engineering Division

APPROVAL RECOMMENDED:

*Joe B. Fryar*

JOE B. FRYAR  
Chief, Engineering Division



## PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Inspections. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Inspection is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigations and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I Inspection; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions be detected.

Phase I Inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established guidelines, the Spillway Test Flood is based on the estimated Probable Maximum Flood for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and variety of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aide in determining the need for more detailed hydrologic and hydraulic studies considering the size of the dam, its general condition and the downstream damage potential.

The Phase I Inspection does not include an assessment of the need for fences, gates, "no trespassing" signs, repairs to existing fences and railings and other items which may be needed to minimize trespass and provide greater security for the facility and safety to the public. An evaluation of the project for compliance with Occupational Safety and Hazard Administration's (OSHA) rules and regulations is also excluded.



## TABLE OF CONTENTS

	<u>Page</u>
Letter of Transmittal	
Brief Assessment	
Review Board Page	
Preface . . . . .	1
Table of Contents . . . . .	ii-iv
Overview Photo	
Location Map	
<u>Section</u>	
1. PROJECT INFORMATION	
1.1 General . . . . .	1
a. Authority . . . . .	1
b. Purpose of Inspection . . . . .	1
1.2 Description of Project . . . . .	1
a. Location . . . . .	1
b. Description of Dam and Appurtenances . . . . .	2
c. Size Classification . . . . .	2
d. Hazard Classification . . . . .	2
e. Ownership . . . . .	3
f. Operator . . . . .	3
g. Purpose of Dam . . . . .	3
h. Design and Construction History . . . . .	3
i. Normal Operational Procedure . . . . .	3
1.3 Pertinent Data . . . . .	3
2. ENGINEERING DATA	
2.1 Design Data . . . . .	7
2.2 Construction Data . . . . .	7
2.3 Operation Data . . . . .	7
2.4 Evaluation of Data . . . . .	7
3. VISUAL INSPECTION	
3.1 Findings . . . . .	8
a. General . . . . .	8
b. Dam . . . . .	8
c. Appurtenant Structures . . . . .	8



<u>Section</u>	<u>Page</u>
d. Reservoir Area . . . . .	9
e. Downstream Channel . . . . .	9
3.2 Evaluation . . . . .	9
4. OPERATIONAL AND MAINTENANCE PROCEDURES	
4.1 Operational Procedures . . . . .	10
a. General . . . . .	10
b. Description of any Warning System in Effect . .	10
4.2 Maintenance Procedures . . . . .	10
a. General . . . . .	10
b. Operating Facilities . . . . .	10
4.3 Evaluation . . . . .	10
5. EVALUATION OF HYDRAULIC/HYDROLOGIC FEATURES	
5.1 General . . . . .	11
5.2 Design Data . . . . .	11
5.3 Experience Data . . . . .	11
5.4 Test Flood Analysis . . . . .	11
5.5 Dam Failure Analysis . . . . .	12
6. EVALUATION OF STRUCTURAL STABILITY	
6.1 Visual Observations. . . . .	14
6.2 Design and Construction Data . . . . .	14
6.3 Post-Construction Changes . . . . .	14
6.4 Seismic Stability . . . . .	14
7. ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES	
7.1 Dam Assessment . . . . .	15
a. Condition . . . . .	15
b. Adequacy of Information . . . . .	15
c. Urgency . . . . .	15



<u>Section</u>	<u>Page</u>
7.2 Recommendations . . . . .	15
7.3 Remedial Measures . . . . .	15
a. Operation and Maintenance Procedures . . . . .	16
7.4 Alternatives . . . . .	16

APPENDICES


- APPENDIX A - Inspection Checklist
- APPENDIX B - Engineering Data
- APPENDIX C - Photographs
- APPENDIX D - Hydrologic and Hydraulic Computations
- APPENDIX E - Information as Contained in the National  
Inventory of Dams






PARKS POND DAM





QUADRANGLE DANBURY, CT

US ARMY, CORPS OF ENGINEERS  
NEW ENGLAND DIVISION  
WALTHAM, MASS.



LOCATION MAP



PHASE I INSPECTION REPORT  
PARKS POND DAM CT 00071

SECTION 1 - PROJECT INFORMATION

1.1 General

a. Authority - Public Law 92-367, August 8, 1972 authorized the Secretary of the Army, through the Corps of Engineers, to initiate a National Program of Dam Inspections throughout the United States. The New England Division of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the New England Region. Storch Engineers has been retained by the New England Division to inspect and report on selected dams in the State of Connecticut. Authorization and notice to proceed were issued to Storch Engineers under a letter of March 6, 1980 from William E. Hodgson, Jr., Colonel, Corps of Engineers. Contract No. DACW33-80-C-0035 has been assigned by the Corps of Engineers for this work.

b. Purpose of Inspection -

(1) Perform technical inspection and evaluation of non-Federal dams to identify conditions which threaten the public safety and thus permit correction in a timely manner by non-Federal interests.

(2) Encourage and prepare the states to initiate quickly effective dam safety programs for non-Federal dams.

(3) To update, verify and complete the National Inventory of Dams.

1.2 Description of Project

a. Location - The Parks Pond Dam is located approximately 1 mile southeast of the intersection of Route 7 and Interstate 84 in the City of Danbury.



Connecticut (See Location Map). The coordinates of the dam are approximately 41°-22.5' north latitude and 73°-27' west longitude. The dam is located on Parks Pond Brook in the Housatonic River Basin.

b. Description of Dam and Appurtenances - Parks Pond Dam is a cyclopean masonry/earth embankment that is 180 feet long and 12 feet high. The earth embankment is on the downstream side and has a 2:1 slope. The upstream face is cyclopean masonry with a vertical face.

The spillway is located on the southern half of the dam and consists of a 30.5-foot long concrete weir that drops 10 feet to a stilling basin.

There is a lower gate house with a valve to control a discharge pipe that passes through the base of the dam. The location of the inlet or the outlet of the pipe is not known. The size of the pipe is unknown and the valve is inoperable.

c. Size Classification - Parks Pond Dam has a maximum height of 12 feet and a maximum storage of 100 acre-feet at the top of the dam. In accordance with the Recommended Guidelines for Safety Inspection of Dams established by the Corps of Engineers, the dam is classified as small (height less than 40 feet and storage less than 1,000 acre-feet).

d. Hazard Classification - Parks Pond Dam is classified as having a significant hazard potential. Failure of the dam could result in the loss of a few lives and cause significant property damage. Approximately 300 feet downstream are several homes where a culvert carries the discharge from the spillway under the neighborhood. First floor sills of the homes in the area of impact are approximately 4 feet above the streambed. Estimated flow and water depths just prior to dam failure at this location is 235 cfs at 1.5 feet and just after dam failure is 2,795 cfs at 5.5 feet.



e. Ownership - The Parks Pond Dam is owned by:

Mr. Paul d'Evegne  
21 Sunset Drive  
Danbury, Connecticut 06810

f. Operator - The person in charge of day-to-day operation of the dam is the owner of the dam.

g. Purpose of Dam - The dam impounds the Parks Pond which is used strickly for recreation.

h. Design and Construction History - There are no design computations or drawings.

i. Normal Operational Procedure - There are no normal operational procedures.

### 1.3 Pertinent Data

a. Drainage Area - Parks Pond drainage basin is in the City of Danbury and is rectangular in shape. The area of the drainage basin is 320 acres (Appendix D - Plate 3). Approximately 5 percent of the drainage basin is natural storage and approximately 95 percent is undeveloped. The topography is hilly with elevations ranging from 950 (NGVD) to 488.2 (NGVD) at the spillway crest.

b. Discharge at Damsite - There are no records available for discharge at the dam.

(1) Outlet works (conduit) size:	unknown
Invert elevation (feet above NGVD):	unknown
Discharge Capacity at top of dam:	unknown
(2) Maximum known flood at damsite:	unknown
(3) Ungated spillway capacity at top of dam:	235 cfs
Elevation (NGVD):	490.2
(4) Ungated spillway capacity at test flood elevation:	302 cfs



	Elevation (NGVD):	490.7
(5)	Gated spillway capacity at normal pool elevation:	N/A
	Elevation (NGVD):	N/A
(6)	Gated spillway capacity at test flood elevation:	N/A
	Elevation:	N/A
(7)	Total spillway capacity at test flood elevation:	302 cfs
	Elevation (NGVD):	490.7
(8)	Total project discharge at top of dam:	235 cfs
	Elevation (NGVD):	490.2
(9)	Total project discharge at test flood elevation:	445 cfs
	Elevation (NGVD):	490.7
c.	Elevation (feet above NGVD)	
(1)	Streambed at toe of dam:	476.2
(2)	Bottom of cutoff:	unknown
(3)	Maximum tailwater:	480
(4)	Normal pool:	488.2
(5)	Full flood control pool:	N/A
(6)	Spillway crest (ungated):	488.2
(7)	Design surcharge (original design):	unknown
(8)	Top of dam:	490.2
(9)	Test flood surcharge:	490.7
d.	Reservoir (length in feet)	
(1)	Normal pool:	2,300



	(2) Flood control pool:	N/A
	(3) Spillway crest pool:	2,300
	(4) Top of dam:	2,500
	(5) Test flood pool:	2,525
e.	Storage (acre-feet)	
	(1) Normal pool:	55
	(2) Flood control pool:	N/A
	(3) Spillway crest pool:	55
	(4) Top of dam:	100
	(5) Test flood pool:	110.5
f.	Reservoir Surface (acres)	
	(1) Normal pool:	13.7
	(2) Flood control pool:	N/A
	(3) Spillway crest:	13.7
	(4) Test flood pool:	22
	(5) Top of dam:	20
g.	Dam	
	(1) Type:	cyclopean masonry/ downstream earth embankment
	(2) Length:	180 feet
	(3) Height:	12 feet
	(4) Top width:	5 feet
	(5) Side slopes:	U/S - vertical D/S - 2:1
	(6) Zoning:	unknown



(7) Impervious core:	unknown
(8) Cutoff:	unknown
(9) Grout curtain:	unknown
(10) Other:	N/A
h. Diversion and Regulating Tunnel	N/A
i. Spillway	
(1) Type:	concrete-broad crested
(2) Length of weir:	30.5 feet
(3) Crest elevation (without flashboard):	488.2
(4) Gates:	N/A
(5) U/S channel:	no channel
(6) D/S channel:	30-foot
	natural channel
(7) General:	N/A
j. Regulating Outlets	
(1) Invert elevation (NGVD):	unknown
(2) Size:	unknown
(3) Description:	unknown
(4) Control Mechanism:	manually operated gate
(5) Other:	gate not operable



## SECTION 2 - ENGINEERING DATA

### 2.1 Design Data

There are no design computations or drawings available.

### 2.2 Construction Data

There are no records or drawings available for the construction of the dam.

### 2.3 Operation Data

Any type of operation at this dam is nonexistent. There is a discharge pipe but it is not operating.

### 2.4 Evaluation of Data

- a. Availability - There were no computations or drawings available.
- b. Adequacy - The information made available along with the visual inspection, past performance history and hydraulic/hydrologic assumptions were adequate to assess the condition of the facility.
- c. Validity - Due to the lack of available data, the conclusions and recommendations found in this report are based on the visual inspection and hydraulic/hydrologic computations.



## SECTION 3 - VISUAL INSPECTION

### 3.1 Findings

a. General - The visual inspection was conducted on April 22, 1980 by members of the engineering staff of Storch Engineers, D. Baugh and Associates, Inc. and Matthews Associates. A copy of the visual inspection check list is contained in Appendix A of this report. Selected photos of the dam and appurtenant structures are contained in Appendix C.

In general, the overall appearance and condition of the facility and its appurtenant structures is poor.

b. Dam - The dam is a cyclopean masonry/earth embankment. The downstream face is an earth embankment with a 2:1 slope. It is well vegetated with grass, brush and trees (Photos 1, 2 and 3). Along the toe of the dam, there are trees and brush which obscured the view of the toe (Overview Photo). The upstream face is cyclopean masonry and is eroded and cavitated at the water line (Photo 1). The top of the masonry is 5 feet wide and it too is cavitated (Photo 2). The top of the dam is level with no signs of settlement. The overall alignment of the dam is good and there are no signs of the dam ever being overtopped.

Just below the toe of the dam and around the west spillway training wall, there is a steady seepage flow (Photo 6). The amount of flow is negligible. This seepage is clear and does not show any signs of particle movement.

c. Appurtenant Structures - The lower gate house (Photos 7 and 8) is in poor condition with the walls and roof slab falling in. The valve inside the house is frozen closed and not operating. There is also some seepage coming



through the dirt floor of the gate chamber (Photo 8). The amount of flow is negligible. The seepage is a rust color which would indicate it is coming from the discharge pipe or valve.

The spillway is a concrete weir that is in poor condition (Photos 3 and 5). The concrete of the spillway is eroded and cavitaded. There is no approach channel. The downstream channel is a natural channel (Photo 4). Just below the spillway, brush and debris has accumulated (Photo 3).

d. Reservoir Area - The area immediately adjacent to the dam is gently sloped and the remainder of the area is fairly steep and wooded. The shoreline shows no signs of sloughing or erosion and there is no development adjacent to the reservoir. A rapid rise in the water level of the reservoir will not endanger any life or property.

e. Downstream Channel - The downstream channel is in a natural state (Photo 4).

### 3.2 Evaluation

Overall, the general condition of the dam is poor. The visual inspection revealed items that lead to this assessment, and apparent areas of distress such as:

- a. Seepage through the embankment and around the training wall.
- b. Inoperation of the blowoff.
- c. Poor condition of the concrete.
- d. Brush and trees are growing on the downstream face of the dam along the toe and in the downstream channel.



## SECTION 4 - OPERATIONAL AND MAINTENANCE PROCEDURES

### 4.1 Operational Procedures

a. General - The operation of this facility is strictly for the purpose of recreation and the water level is kept at or above spillway crest only because the discharge pipe and valve are not operating.

b. Description of any Warning System in Effect - There is no warning system in effect for this dam.

### 4.2 Maintenance Procedures

a. General - This dam appears to be given the very minimum of maintenance.

b. Operating Facilities - The valve is not operable.

### 4.3 Evaluation

The maintenance of the dam is less than adequate in that proper care of the dam embankment should be on a regular basis. The valve should be maintained in working order and there should be a proper operating procedure and warning system in effect.



## SECTION 5 - EVALUATION OF HYDRAULIC/HYDROLOGIC FEATURES

### 5.1 General

Parks Pond Dam is a cyclopean masonry/earth embankment approximately 180 feet long and 12 feet high. The spillway is a concrete weir, 30.5 feet long. The downstream channel is 30 feet wide and is a natural state. A discharge pipe passes through the base of the dam. The size of the pipe is not known and the valve is inoperable.

The watershed encompasses 0.5 square miles and is 95 percent undeveloped. The topography is hilly with the terrain rising 461.8 feet from the spillway crest.

The pond has a total capacity of 100 acre-feet when the pond is at the top of the embankment and 55 acre-feet at the spillway crest. Therefore, there is approximately 45 acre-feet of storage available. The test flood outflow for this dam is 445 cfs and the spillway capacity is 235 cfs or approximately 52.8% of the test flood outflow.

### 5.2 Design Data

No design data is available.

### 5.3 Experience Data

Parks Pond Dam has experienced all the major storms of the 1930's and 1950's and most recently January, 1979. The flood of record resulted from the storm of October, 1955. No records are available for this flood, however, a past inspection report revealed that the dam was probably not overtopped during this storm.

### 5.4 Test Flood Analysis

Based on the guidelines found in the Recommended Guidelines for Safety Inspection of Dams, the dam is classified as a small structure with a significant



hazard potential. The test flood for these conditions range from the 100-year flood to 1/2 the Probable Maximum Flood. One half the PMF was used for this dam because of the possible loss of life.

Using the guide curves established by the Corps of Engineers (rolling terrain), the test flood inflow is 625 cfs. The routing procedure established by the Corps gives an approximate outflow of 445 cfs. The spillway capacity is approximately 235 cfs or approximately 52.8% of the test flood outflow. The test flood will overtop the dam by approximately 0.5 feet.

Storage behind the dam was assumed to begin at the spillway crest. Storage was determined by an average area depth analysis. Capacity curves for the spillway assumed a broad crested weir.

#### 5.5 Dam Failure Analysis

A dam failure analysis was performed using the Rule of Thumb method in accordance with guidelines established by the Corps of Engineers. Failure was assumed to occur when the water level in the reservoir was at the top of the dam.

The spillway discharge just prior to dam failure is 235 cfs and will produce a depth of flow of approximately 1.5 feet several hundred feet downstream from the dam. The calculated dam failure discharge is 2,795 cfs and will produce a depth of flow of approximately 5.5 feet several hundred feet downstream from the dam or an increase in water depth at failure of approximately 4 feet. The failure analysis covered a distance of approximately 6,800 feet downstream where the depth of flow was calculated to be 3 feet or an increase in depth of 1.5 feet.

Failure of Parks Pond Dam may result in the loss of a few lives. Damage to structures, personal property and town roads may be appreciable



for several thousand feet downstream. Approximately 300 feet downstream are several homes where a culvert carries the discharge from the spillway under the neighborhood. First floor sills of the homes in the area of impact are approximately 4 feet above the streambed. Estimated flow and water depths just prior to dam failure at this location is 235 cfs at 1.5 feet and just after dam failure is 2,795 cfs at 5.5 feet.



## SECTION 6 - EVALUATION OF STRUCTURAL STABILITY

### 6.1 Visual Observations

The general structural stability of the dam is good as evidenced by the vertical, horizontal and lateral alignment of the embankment. The upstream face of the dam is severely eroded and cavitated at the water line. The embankment is in good stable condition and has a good vegetative cover, however, there are some large trees growing on it. The concrete of the spillway weir, like the rest of the dam, is in poor condition. The outlet chamber is in poor condition.

Some possible problem areas are seepage around the spillway training walls, through the gate chamber floor and the poor condition of the concrete.

### 6.2 Design and Construction Data

No design data or construction drawings are available.

### 6.3 Post-Construction Changes

No information on post-construction changes are available.

### 6.4 Seismic Stability

The dam is located in Seismic Zone 1 and in accordance with Recommended Phase I Guidelines does not warrant a seismic analysis.



## SECTION 7 - ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES

### 7.1 Dam Assessment

a. Condition - After consideration of the available information, the results of the inspection, contact with the owner and hydraulic/hydrologic computations, the general condition of the Parks Pond Dam is fair.

b. Adequacy of Information - The information available is such that an assessment of the safety of the dam should be based on the available data, the visual inspection results, past operational performance of the dam and its appurtenant structures and computations developed for this report.

c. Urgency - It is considered that the recommendations suggested below be implemented within one year after receipt of this Phase I Inspection Report.

### 7.2 Recommendations

The following recommendations should be carried out under the direction of a qualified registered engineer.

- a. Seepage around the spillway training wall and in the gate chamber should be investigated further to determine its origin and monitored to determine any changes.
- b. Trees including stumps and root systems should be removed from the toe and embankment slopes and backfilled with proper material.
- c. Prepare a detailed hydraulic/hydrologic study to determine spillway adequacy and an increase of the total project discharge if necessary.



### 7.3 Remedial Measures

#### a. Operation and Maintenance Procedures -

- (1) Spillway channel should be cleared of brush and debris.
- (2) Vegetation on the downstream face of the dam and along the toe of the dam should be removed. This will facilitate the visual observation of existing and potential seepage.
- (3) Discharge valve and pipe should be repaired. Valve for the discharge pipe should be on the upstream side of the embankment.
- (4) Concrete of the dam, spillway and training walls should be repaired.
- (5) Plans for a regular program of operation and maintenance of the dam should be initiated.
- (6) Plans for around-the-clock surveillance should be developed for periods of unusually heavy rains and a formal downstream warning system should be put into operation for use in the event of an emergency.
- (7) A program of annual technical inspection should be established.

### 7.4 Alternatives

None.



APPENDIX A

INSPECTION CHECK LIST



# INSPECTION CHECK LIST

## PARTY ORGANIZATION

PROJECT PARKS POND DAM

DATE 4/22/80

TIDE 8:30 a.m.

WEATHER Clear

W.S. ELEV. \_\_\_\_\_ U.S. \_\_\_\_\_ D.N.S.

### PARTY:

- |                                          |                                   |
|------------------------------------------|-----------------------------------|
| 1. <u>John F. Schearer, SE Civil</u>     | 6. <u>John Pozzato, MA, Mech.</u> |
| 2. <u>Kenneth J. Pudeler, SE Civil</u>   | 7. _____                          |
| 3. <u>Gary J. Giroux, SE Hyd/Civil</u>   | 8. _____                          |
| 4. <u>Michael Haire, DBA Struct/Geo.</u> | 9. _____                          |
| 5. <u>Peter Austin, DBA Civil</u>        | 10. _____                         |

PROJECT FEATURE	INSPECTED BY	REMARKS
1. _____		
2. _____		
3. _____		
4. _____		
5. _____		
6. _____		
7. _____		
8. _____		
9. _____		
10. _____		



# INSPECTION CHECK LIST

PROJECT PARKS, POND DAM DATE 4/22/80  
 PROJECT FEATURE \_\_\_\_\_ NAME \_\_\_\_\_  
 DISCIPLINE \_\_\_\_\_ NAME \_\_\_\_\_

AREA EVALUATED	CONDITIONS
<u>DAM EMBANKMENT</u>	
Crest Elevation	Fair
Current Pool Elevation	Poor - eroded concrete
Maximum Impoundment to Date	Unknown
Surface Cracks	None
Pavement Condition	N/A
Movement or Settlement of Crest	None observed
Lateral Movement	None
Vertical Alignment	Good
Horizontal Alignment	Good
Condition at Abutment and at Concrete Structures	Fair
Indications of Movement of Structural Items on Slopes	Outlet structure: appears walls have been pushed or heaved
Trespassing on Slopes	Problem
Vegetation on Slopes	Trees and brush
Sloughing or Erosion of Slopes or Abutments	None observed
Rock Slope Protection - Riprap Failures	N/A
Unusual Movement or Cracking at or near Toes	None
Unusual Embankment or Downstream Seepage	Minor seepage - almost negligible
Piping or Boils	None
Foundation Drainage Features	None
Toe Drains	None
Instrumentation System	None



**INSPECTION CHECK LIST****PROJECT** PARKS POND DAM**DATE** 4/22/80**PROJECT FEATURE** **NAME** **DISCIPLINE** **NAME** 

AREA EVALUATED	CONDITION
<p data-bbox="277 521 796 585"><u>CUTLET WORKS - INTAKE CHANNEL AND INTAKE STRUCTURE</u></p> <p data-bbox="277 612 596 644">a. Approach Channel</p> <p data-bbox="376 676 627 708">Slope Conditions</p> <p data-bbox="376 740 644 772">Bottom Conditions</p> <p data-bbox="376 804 690 836">Rock Slides or Falls</p> <p data-bbox="376 868 508 900">Log Boom</p> <p data-bbox="376 932 475 963">Debris</p> <p data-bbox="376 995 817 1027">Condition of Concrete Lining</p> <p data-bbox="376 1059 693 1091">Drains or Weep Holes</p> <p data-bbox="277 1123 602 1155">b. Intake Structure</p> <p data-bbox="376 1187 710 1219">Condition of Concrete</p> <p data-bbox="376 1251 682 1283">Stop Logs and Slots</p>	<p data-bbox="921 532 1495 563">No intake structure observed underwater</p>



# INSPECTION CHECK LIST

PROJECT PARKS POND DAM

DATE 4/22/80

PROJECT FEATURE \_\_\_\_\_

NAME \_\_\_\_\_

DISCIPLINE \_\_\_\_\_

NAME \_\_\_\_\_

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - CONTROL TOWER</u>	None N/A
a. Concrete and Structural	
General Condition	
Condition of Joints	
Spalling	
Visible Reinforcing	
Rusting or Staining of Concrete	
Any Seepage or Efflorescence	
Joint Alignment	
Unusual Seepage or Leaks in Gate Chamber	
Cracks	
Rusting or Corrosion of Steel	
b. Mechanical and Electrical	
Air Vents	
Float Wells	
Crane Hoist	
Elevator	
Hydraulic System	
Service Gates	
Emergency Gates	
Lightning Protection System	
Emergency Power System	
Wiring and Lighting System in Gate Chamber	



**INSPECTION CHECK LIST**PROJECT PARKS POND DAMDATE 4/22/80

PROJECT FEATURE \_\_\_\_\_

NAME \_\_\_\_\_

DISCIPLINE \_\_\_\_\_

NAME \_\_\_\_\_

**AREA EVALUATED****CONDITION****OUTLET WORKS - TRANSITION AND CONDUIT**

Unknown - underwater or under dam

General Condition of Concrete

Rust or Staining on Concrete

Spalling

Erosion or Cavitation

Cracking

Alignment of Monoliths

Alignment of Joints

Numbering of Monoliths



# INSPECTION CHECK LIST

PROJECT PARKS POND DAM

DATE 4/22/80

PROJECT FEATURE \_\_\_\_\_

NAME \_\_\_\_\_

DISCIPLINE \_\_\_\_\_

NAME \_\_\_\_\_

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - OUTLET STRUCTURE AND OUTLET CHANNEL</u>	
General Condition of Concrete	Poor - on the verge of collapse
Rust or Staining	None
Spalling	None
Erosion or Cavitation	N/A
Visible Reinforcing	Yes
Any Seepage or Efflorescence	Yes - seepage in ground
Condition at Joints	Very poor
Drain holes	None observed
Channel	Could not find
Loose Rock or Trees Overhanging Channel	" " "
Condition of Discharge Channel	" " "



# INSPECTION CHECK LIST

PROJECT PARKS POND DAM

DATE 4/22/80

PROJECT FEATURE \_\_\_\_\_

NAME \_\_\_\_\_

DISCIPLINE \_\_\_\_\_

NAME \_\_\_\_\_

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - SPILLWAY WEIR, APPROACH AND DISCHARGE CHANNELS</u>	
a. Approach Channel	Underwater
General Condition	
Loose Rock Overhanging Channel	
Trees Overhanging Channel	
Floor of Approach Channel	
b. Weir and Training Walls	
General Condition of Concrete	Poor
Rust or Staining	None
Spalling	Yes - eroded at base
Any Visible Reinforcing	No - appears unreinforced
Any Seepage or Efflorescence	Some
Drain Holes	None
c. Discharge Channel	
General Condition	Fair
Loose Rock Overhanging Channel	None
Trees Overhanging Channel	Yes
Floor of Channel	Some natural rock, some silting
Other Obstructions	Debris at base of spillway



# INSPECTION CHECK LIST

PROJECT PARKS POND DAM

DATE 4/22/80

PROJECT FEATURE \_\_\_\_\_

NAME \_\_\_\_\_

DISCIPLINE \_\_\_\_\_

NAME \_\_\_\_\_

AREA EVALUATED	CONDITION
<p><u>OUTLET WORKS - SERVICE BRIDGE</u></p> <p>a. Super Structure</p> <p>Bearings</p> <p>Anchor Bolts</p> <p>Bridge Seat</p> <p>Longitudinal Members</p> <p>Under Side of Deck</p> <p>Secondary Bracing</p> <p>Deck</p> <p>Drainage System</p> <p>Railings</p> <p>Expansion Joints</p> <p>Paint</p> <p>b. Abutment &amp; Piers</p> <p>General Condition of Concrete</p> <p>Alignment of Abutment</p> <p>Approach to Bridge</p> <p>Condition of Seat &amp; Backwall</p>	<p>N/A</p>



APPENDIX B

ENGINEERING DATA



Information pertaining to the history, maintenance and modification to  
Parks Pond Dam as well as copies of past reports are located at:

State of Connecticut  
Department of Environmental Protection  
Water Resources Unit  
State Office Building  
Hartford, Connecticut 06115



A. M. MCKENZIE

CIVIL ENGINEER

MEM. H. AN. SEC. C. S.

1800 MAIN STREET  
SOUTH MERIDEN, CONN.

September 27, 1936.

↓  
1963

Water Resources Commission,  
State of Connecticut,  
State Office Building,  
Hartford, 15,  
Connecticut.

Terrywile Lake  
(Parks Pond)  
Danbury

Ref:

Owner - Terrywile Realty Co.,  
45 West St.,  
Danbury, Conn.  
H. D. Van Houten, V. P.

Gentlemen:

There are three ponds involved in this property but this report is concerned principally with the dam on the middle pond which is by far the largest of the three. It is about 2800 feet long and greatest width is about 700 feet. The water area at spillway elevation is about 32 acres. A commercial map of the City of Danbury shows the ponds just outside the city limits, south of Southern Boulevard and west of Terrywile Lake Drive. The area around the north end of the ponds is a thickly built-up residential section. The dam is about a mile east, and a little south of the Danbury Fair Grounds and can be most easily approached from Route 7, via Southern Blvd.

2. The deterioration of the dam on the middle pond does not seem to be serious at this time. It consists of erosion of the concrete at the water line on the upstream face, the entire surface of the spillway and the lower part of the spillway wingwalls.

If the dam failed during a flood there could be serious damage to property downstream - loss of life not probable.

If the dam failed during ordinary flows there might be damage to property downstream - loss of life unlikely.

There are city streets and a residence lot under which the discharge from the lake passes; see later comment on concrete pipe culvert

3. The dam seems to be of cyclopean masonry judging from the boulders protruding from the top and sides of the structure. The downstream side is backed by earth fill which shows no signs of erosion. On the west side of the spillway the downstream slope is thickly planted with pine trees from 4" to 15"; the slope on the other side of the spillway is covered with grass and brush. The over-all length of the dam is 180' with a 32' spillway. See sketch and photos for details.



A. M. MCKENZIE

CIVIL ENGINEER

MEM. N. AM. SOC. C. E.

PAGE - 2 -

1200 MAIN STREET  
SOUTH MERIDEN, CONN.

3. (cont.)

There is no information available on the foundation of the dam. There are no visible rock out-croppings in the immediate vicinity and my guess is that the dam is founded on the material of the original stream bed which is probably gravel.

The original spillway surface might have been an "ogee" section but the shape is now quite irregular and rough. Based on a possible original section the capacity might have been about 300 c.f.s. In it's present condition I would reduce the capacity to 65% - say 200 c.f.s.

The existing freeboard is 2' - if this is not maintained the earth fill might be washed out. Not considered serious at this time.

There are no visible leaks thru or under the dam at this date. No cracks or displacement was observed. There is very considerable erosion along the water line, upstream face, and at the bottom of the wing walls on the inside face. The entire downstream face of the spillway is eroded and quite rough. See sketch and photos for more detail.

4. The drainage area above the dam is about 0.6 square miles, quite steep and thickly wooded.

The best data regarding possible peak discharge from the water shed is that given in Paper 1662, Proceedings of the A. S. C. E., Actual observed discharges of small streams, comparable to the stream under consideration here, and in the immediate vicinity, vary from 360 c.f.s to over 1100 c.f.s. These figures are for the floods in the fall of 1955 which are the largest ever recorded in the New England States. These quantities are much greater than any ordinarily used formula will give.

The estimated capacity of the spillway in it's existing condition is 200 c.f.s.

It is not likely that floods equal to those of 1955 will occur again in the next 50 years and there is no evidence to indicate that the capacity of the spillway was exceeded in 1955.

5. The dam does not appear to be unsafe at the present time and periodic inspections should not be necessary if the repairs are made within the next year.

6. The water in the lake should be lowered about 3' so that the damaged masonry at the water line on the upstream face, the entire face of the spillway and the lower part of the wingwalls ~~can~~ be cleaned up and the structure restored by pouring new concrete. See sketch indicating possible method of making repairs. A few feet outside the lower end of the east wingwall there is what appears to be the top of a gate valve on a drain thru the dam. The valve might be 10" or 12" in diameter; neither end of the pipe is visible. The valve is covered by a badly disintegrated concrete enclosure perhaps 4' x 7' inside. The drain should be cleaned and the



A. M. MCKENZIE

CIVIL ENGINEER

MEM. D. AM. SOC. C. E.

1800 MAIN STREET  
SOUTH MERIDEN, CONN.

PAGE - 3 -

6. (cont.)

valve repaired or replaced so that there will be some way of controlling the water level in the lake.

It is probably too late to start repairs on the dam this year; the work could be most advantageously done during the dry season next year.

It is not considered that any immediate action is required at this time. The structure is basically sound and stable and, barring some unpredictable catastrophe, is safe for another winter season.

The only immediate problem which this investigation brings out is the 30"  $\phi$  culvert which carries the entire discharge from the Terry Wile ponds under Terrywile Lake Drive and Southern Boulevard and spills it into an open channel. This culvert seems to cross private property for a part of it's length.

The culvert is about 250' long with a slope of about 4' in 100'. The intake is a circular masonry wall just a few feet below the spillway of the lower of the three ponds. See photo. The pipe seems to be in good condition and, based on a value of "n" equals .015 in Manning's formula, will have a maximum capacity of about 45 c.f.s. Assuming that the maximum capacity of the dam, 200 c.f.s. might be reached, it is obvious that the culvert is much too small. During the unusual floods of 1955 the culvert was greatly overloaded, the stream washing over the streets and lawns and doing considerable damage. The exact runoff, or discharge, at this time is not known.

To at least partially correct this situation I recommend that additional culvert capacity be provided. The most economical procedure might be to install a new 48"  $\phi$  R.C.P. culvert alongside the existing 30"  $\phi$  or to replace the 30" with a new 60"  $\phi$  pipe. Either scheme will give a capacity of 130 c.f.s. This operation could well be carried out any time before next year's spring floods.

7. & 8. The middle pond dam was probably built 50, or more years ago and there is no evidence of it's having been damaged by floods, including those of 1955, which were the highest on record in this area. Therefore, I am of the opinion that the existing spillway, when properly repaired will have sufficient capacity for the foreseeable future. The additional culvert capacity should be provided at once. The normal flow over the spillway is very small; on the date of the inspection it was less than 1 c.f.s

9. It does not appear that an order to repair the dam has to be issued at this time. A letter of advice should be sent to the owner describing the condition and suggested repairs. The culvert situation should be corrected before the spring flood season of 1964. It is possible that the City of Danbury is responsible for the culvert carrying the flow from the ponds.



A. M. MCKENZIE

CIVIL ENGINEER

MEM. B. AM. SOC. C. E.


1800 MAIN STREET  
SOUTH MERIDEN, CONN.

PAGE - 4 -

The Terrywile Lake appears partly on the Danbury sheet and partly on the Bethel sheet of the U. S. C. & G. Survey Topographic Maps.

Mr. Muchmore's letter refers to the culvert under Southern Boulevard as being 24"  $\phi$  - I believe that it is actually 30"  $\phi$

Yours very truly



A. M. McKenzie.

Enclosures:

- 6 - photographs
- 1 - sketch showing some details of the dam
- 1 - sketch indicating approximate location of 30"  $\phi$  concrete pipe drain under Terrywile Lake Drive and Southern Blvd.



N (Approx.)



Southern

BVA

30" R.C.P. 1850'

Stone Masonry Wall

Lower Pond

See Danbury Quad.  
U.S.C. & G.S. Topo Map.

also - Danbury Street Map.

Dam is about E+W.

Terryville  
LAKE DRIVE

APR 3


± 200'

Dam 2

SPILLWAY

182'

TERRYWILE LAKE  
(Parks Pond)











9/21/63


# TERRYWILE LAKE DAM. (PARKS POND) DANBURY.



Possible Method of  
Repairing Masonry




SECT. - X-X Thru Spillway  
Scale  $\frac{1}{8}" = 1'-0"$





PLAN  
 $1" = 20'$   
EXISTING DAM





**SECTION B-B**



**SECTION A-A**






PLATE 1

STORCH ENGINEERS WETHERSFIELD, CONNECTICUT	U.S. ARMY ENGINEER DIV NEW ENGLAND CORPS OF ENGINEERS WALTHAM MASS
NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS	
PARKS POND DAM	
	SCALE AS SHOWN DATE JULY 1980

NOT TO SCALE




APPENDIX C


PHOTOGRAPHS



PARKS POND







PARKS POND

Flow Line

100'

Top Of Dam

5'

Earth Embankment

5'

Seepage Area

Overview Photo

**PLAN**

**PHOTO LOCATION PLAN**

**PLATE 2**

STORCH ENGINEERS WETHERSFIELD,CONNECTICUT		U.S. ARMY ENGINEER DIV NEW ENGLAND CORPS OF ENGINEERS WALTHAM MASS	
NATIONAL PROGRAM OF INSPECTION OF NON-FED.DAMS			
PARKS POND DAM			
			SCALE AS SHOWN
			DATE JULY 1980

**NOT TO SCALE**

2





PHOTO 1  
UPSTREAM FACE OF DAM




PHOTO 2  
CREST OF DAM





PHOTO 3  
SPILLWAY - UPSTREAM



PHOTO 4  
VIEW LOOKING DOWNSTREAM





PHOTO 5  
CONCRETE CAVITATION AT SPILLWAY



PHOTO 6  
SEEPAGE AT TOE OF SPILLWAY WINGWALL





PHOTO 7  
GATE HOUSE



PHOTO 8  
SEEPAGE - INSIDE GATE HOUSE



## APPENDIX D

### HYDROLOGIC AND HYDRAULIC COMPUTATIONS





**PLATE 3**

**STORCH ENGINEERS**  
WETHERSFIELD, CONNECTICUT

**U.S. ARMY ENGINEER DIV NEW ENGLAND**  
**CORPS OF ENGINEERS**  
WALTHAM MASS

**NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS**

**PARKS POND DAM**

**SCALE AS SHOWN**  
**DATE JULY 1980**



**STORCH ENGINEERS**  
Engineers - Landscape Architects  
Planners - Environmental Consultants

JOB Phase I Dam Inspection - #4463

SHEET NO 1

OF 7

CALCULATED BY GJG

DATE 7/25/80

CHECKED BY BDC

DATE 7/15/80

**Determination of PMF**

NAME OF DAM PARKS POND DAM

DRAINAGE AREA 0.5 SM

INFLOW  $\frac{1}{2}PMF = 1250 \text{ cfs/SM}$

$$\frac{1}{2}PMF = 1250(.5) = 625 \text{ cfs}$$

$$Q_{100} = 340 A^{.79} = 340 (.5)^{.79} = 197 \text{ cfs}$$

**Estimating the effect of surcharge storage on the Maximum Probable Discharges**

1.  $Q_{p1} = \underline{625} \text{ cfs}$

2a.  $H_1 = \underline{2.8'} \text{ (elev.)}$

b.  $STOR_1 = \underline{2.4''}$

c.  $Q_{p2} = Q_{p1} (1 - STOR_1/9.5) = \underline{464} \text{ cfs}$

3a.  $H_2 = \underline{2.55'}$   $STOR_2 = \underline{2.06''}$

b.  $STOR_A = \underline{2.31''}$

$$Q_{PA} = 625(1 - \frac{2.31}{9.5}) = 473 \text{ cfs}$$

$H_A = \underline{2.55'}$   $STOR_A = \underline{2.0''}$

$\frac{1}{2}PMF = \underline{473} \text{ cfs}$

$Q_{100}$

200

1.83'

1.5"

138 cfs

1.5'

1.35"

146 cfs

1.5'

1.2"

**Capacity of the spillway when the pond elevation is at the top of the dam**

$Q = \underline{235} \text{ cfs or } \underline{49.7} \% \text{ of the } \frac{1}{2}PMF$

$160 \% \text{ of } Q_{100}$



**STORCH ENGINEERS**  
Engineers - Landscape Architects  
Planners - Environmental Consultants

JOB Phase I Dam Inspection 4463

SHEET NO 2 OF 7


CALCULATED BY GJG DATE 4/16/80

CHECKED BY PDC DATE 7/5/80

**AREA - CAPACITY**

Name of Dam: PARKS POND DAM

ELEV	DEPTH	AREA	AVG. AREA	VOL	I VOL
0.0		13.7			0.0
	5.0		22.0	110.0	
5.0		30.3			110
	10.0		38.1	381	
15.0		45.9			491





**STORCH ENGINEERS**  
Engineers - Landscape Architects  
Planners - Environmental Consultants

JOB Phase I Dam Inspection 4463

SHEET NO 3 OF 7

CALCULATED BY EEA DATE 7/12/50


CHECKED BY BDC DATE 7/15/50

SCALE Stage Discharge

NAME OF DAM PARKS POND DAM

$$Q = CLH^{3/2}$$

Elev	Spillway I				Spillway II				Dam				QT
	C	L	H	Q	C	L	H	Q	C	L	H	Q	
	2.65	30.5	.5	28.6					2.65	140	.5	181.2	450.7
	2.65	30.5	1.0	80.8					2.65	140	1.0	371	791
	2.65	30.5	1.5	148.5					2.65	140	1.5	682	
	2.65	30.5	2.0	228.6					2.65	140	2.0	1049	
	2.65	30.5	2.5	319.5									
	2.65	30.5	3.0	420									
	2.65	30.5	3.5	529									
	2.65	30.5	4.0	646.6									





**STORCH ENGINEERS**  
Engineers - Landscape Architects  
Planners - Environmental Consultants

JOB Phase I Dam Inspection - #4463

SHEET NO 41 OF 7

CALCULATED BY E.E.A DATE April 28 1990

CHECKED BY PDC DATE 7/15/90

Downstream Hydrographs

"Rule of Thumb" Guidance for Estimating Downstream Failure Hydrographs

NAME OF DAM PARKS POND DAM.

Section I at Dam

1.  $S = \frac{100}{8/27 W_b \sqrt{g}} \text{ Acft } Y^{3/2} = 8/27 (40) \sqrt{32.2} 12^{3/2} = 2796 \text{ cfs}$
2.  $Q_{p1} = 8/27 W_b \sqrt{g} Y^{3/2} = 8/27 (40) \sqrt{32.2} 12^{3/2} = 2796 \text{ cfs}$
3. See Sections

Section II at

- 4a.  $H_2 = \underline{6'}$   $A_2 = \underline{565 \text{ SF}}$   $L_2 = \underline{2000'}$   $V_2 = \underline{126} \text{ Acft}$
  - b.  $Q_{p2} = Q_{p1} (1 - V_2/S) = \underline{2070} \text{ cfs}$
  - c.  $H_2 = \underline{5.5'}$   $A_2 = \underline{500 \text{ SF}}$   
 $A_A = \underline{533 \text{ SF}}$   $V_2 = \underline{24.5} \text{ Acft}$
- $Q_{p2} = 2796 [1 - 24.5/100] = 210 \text{ cfs}$

Section III at

- 4a.  $H_3 = \underline{5.1'}$   $A_3 = \underline{470 \text{ SF}}$   $L_3 = \underline{1300'}$   $V_3 = \underline{141.0} \text{ Acft}$
  - b.  $Q_{p3} = Q_{p2} (1 - V_3/S) = \underline{1720} \text{ cfs}$
  - c.  $H_3 = \underline{4.8'}$   $A_3 = \underline{400 \text{ SF}}$   
 $A_A = \underline{435 \text{ SF}}$   $V_3 = \underline{13} \text{ Acft}$
- $Q_{p3} = 1720 (1 - 13/75.5) = 1420 \text{ cfs}$

Section IV at


- 4a.  $H_4 = \underline{4.0'}$   $A_4 = \underline{500 \text{ SF}}$   $L_4 = \underline{3500'}$   $V_4 = \underline{40.1} \text{ Acft}$
  - b.  $Q_{p4} = Q_{p3} (1 - V_4/S) = \underline{507} \text{ cfs}$
  - c.  $H_4 = \underline{2.5'}$   $A_4 = \underline{250 \text{ SF}}$   
 $A_A = \underline{375 \text{ SF}}$   $V_4 = \underline{30.1} \text{ Acft}$
- $Q_{p4} = 1420 (1 - 30.1/62.5) = 736 \text{ cfs}$

$H = 3.0'$




**STORCH ENGINEERS/STORCH ASSOCIATES**  
 Engineers • Landscape Architects  
 Planners • Environmental Consultants

SHEET NO. 5 OF 7  
 CALCULATED BY B.A. DATE 5/30/90  
 CHECKED BY B.P.C. DATE 7/16/90  
 SCALE Section II




D	W	A	R	$R^3$	$S^{\frac{1}{2}}$	V	Q
2	80	130	1.62	1.38	.063	2.6	240
5	135	460	3.7	2.25	.063	4.29	1,973
8	190	960	5.0	2.96	.063	5.56	5,340
10	240	1,150	6.6	3.33	.063	6.27	9,100
20	420	4,700	11.2	5.0	.063	9.5	44,550
30	610	9,900	19.2	6.5	.063	12.1	120,400






**STORCH ENGINEERS/STORCH ASSOCIATES**  
 Engineers - Landscape Architects  
 Planners - Environmental Consultants

JOB 21-162  
 SHEET NO 6 OF 7  
 CALCULATED BY BAH DATE 5/24/80  
 CHECKED BY BDC DATE 7/15/80  
 SCALE Section 2



D	W	A	R	R <sup>3</sup>	S <sup>1/2</sup>	V	Q
2	120	195	1.63	1.39	0.09	3.72	725
5	180	638	3.54	2.32		6.21	3562
8	240	1260	5.25	3.02		8.08	10,181
10	250	1325	6.25	3.41		9.12	16,644
20	500	5750	11.50	5.10	↓	13.64	78,430
30	700	11,625	16.01	6.52	0.09	17.44	202,740





**STORCH ENGINEERS/STORCH ASSOCIATES**  
 Engineers • Landscape Architects  
 Planners • Environmental Consultants

JOB 21-103

SHEET NO. 7

OF 7


CALCULATED BY BVH

DATE 5/30/80

CHECKED BY BDC

DATE 5/15/80


SCALE Section IV



$n = .05$   
 $S = .25\%$

D	W	A	R	$R^2$	$S^2$	V	Q
2	130	200	1.5	1.3	.05	1.98	400
5	240	725	3.0	2.09	.05	3.11	2,260
8	310	1560	4.6	2.77	.05	4.1	6,430
10	420	2450	5.8	3.2	.05	4.8	11,870
20	760	8300	10.9	4.96	.05	7.4	61,200
30	1120	17850	15.9	6.39	.05	9.5	169,540

Depth (ft)



Area  
 (1000's of ft<sup>2</sup>)

Discharge (1000's of cfs)

D-7



APPENDIX E

INFORMATION AS CONTAINED IN  
THE NATIONAL INVENTORY OF DAMS



# INVENTORY OF DAMS IN THE UNITED STATES

STATE	DIVISION	COUNTY	CITY	NAME	REPORT DATE
CT	NEO	CT 001	05	PARKS ROAD DAM	10 JUL 60

POPULAR NAME	NAME OF IMPONDMENT
REGION	
RIVER OR STREAM	
NEAREST DOWNSTREAM CITY - TOWN - VILLAGE	
POPULATION	

TYPE OF DAM	YEAR COMPLETED	PURPOSES	HYDRAULIC POWER	IMPONDING CAPACITIES
RLCBBG	1900	R	12	12

REMARKS

D/S	SPILLWAY	MAXIMUM DISCHARGE (CFS)	VOLUME OF DAM (CU YD)	POWER CAPACITY (KW)	INSTALLED	PROPOSED	NAVIGATION LOCKS
2	180	34	235	700			

OWNER	ENGINEERING BY	CONSTRUCTION BY
PAUL D'ELGMEY	NOT KNOWN	NOT KNOWN

DESIGN	CONSTRUCTION	OPERATION	MAINTENANCE

INSPECTION BY	INSPECTION DATE	AUTHORITY FOR INSPECTION
STORCH ENGINEERS	22 APR 60	BL 02-367

REMARKS

DIST QWN FED R PRV/PED SCS A VER/DATE



**DATE**  
**ILME**